Herrick, Will Campton, KY Page 45 of 108

and generate a net output of 205 MW. Later studies^{7,8,11} indicated that higher efficiencies, 51.7% –53.5%, can be achieved with higher methane producing gasifiers and by using hot gas clean-up. More recently¹², studies of hybrid fuel cell/turbine systems have shown that LHV efficiencies of 70% can be achieved on natural gas. This system utilizes a gas turbine as a bottoming cycle to the fuel cell, as shown in Figure 5. This concept can be applied to coal gas systems as well.




Figure 5
High Efficiency Hybrid Fuel Cell/Turbine Power Cycle

Emissions from this plant would be extremely low and below any current or anticipated future standards. Figure 6 compares the combined SOX, NOX, and solid waste emissions of existing commercial technologies, IGCC and IGFC. IGFC technology achieves the lowest levels of pollutant emissions in addition to lower CO₂ emissions and make-up water requirements. The CO₂ emission is 1.54 lb/kWh and the make-up water requirement is 6.8 GPM/MWh.



Figure 6
Environmental Impact Comparison of IGFC and
Other Technologies

 $25^{\rm h}$ International Technical Conference on Coal Utilization and Fuel Systems March 6-9, 2000 in Clearwater, FL Sent on January 24, 2000

Herrick, Will Campton, KY Page 46 of 108

Experimental testing

Experimental testing of a 20 kW sub-scale fuel cell stack was conducted9 at Louisiana Gasification Technology Inc. (LGTI) in 1993-4 by Destec as shown in Figure 7. This was the world's first test of a carbonate fuel cell on coal derived gas. Gas from the entrained flow Destec gasifier was further cleaned-up after bulk gas clean-up by the fuel cell test facility and supplied to the fuel cell. The fuel cell operated on syn gas from the gasifier and interchangeably with natural gas providing normal performance and stable operation.



Figure 7
20 kW Carbonate Fuel Cell Test at the LGTI Gasification
Facility

After completion of the test, the fuel cell was disassembled for post-test inspection. Analysis of the components indicated no evidence of degradation and no detectable accumulation of coal gas borne contaminants in the fuel cell electrolyte or in the hardware. These results paved the way for a larger scale demonstration test.

Clean coal demonstration test

FuelCell Energy is planning to build and test a 2-MW carbonate fuel cell power plant as part of the Kentucky Pioneer Energy Project by Global Energy. The plant will be located in Trapp, KY and will be operational in 2003. This project, supported by DOE as part of the Clean Coal Technology Program will include a 400-MW Integrated Gasification Combined Cycle (IGCC) and a 2-MW fuel cell power plant (Integrated Gasification Fuel Cell, IGCF) as shown in Figure 8. The project will feature Advanced Fuel Technology briquettes made of Kentucky coal and Municipal Solid Waste (MSW) as fuel in the gasification process, adding a renewable fuel component to the project. The use of municipal solid waste as fuel reduces fuel cost to the power plant and provides low cost waste elimination. British Gas/Lurgi (BGL) gasification technology and General Electric advanced turbine power generation will be utilized for the IGCC

As shown in Table 1 emissions from this plant will be significantly lower than conventional coal fired plants using PC boiler, atmospheric fluidized bed, and pressurized fluidized bed technologies.

25th International Technical Conference on Coal Utilization and Fuel Systems March 6-9, 2000 in Clearwater, FL Sent on January 24, 2000 Herrick, Will Campton, KY Page 47 of 108




Figure 8
400-MW IGCC and 2-MW Fuel Cell Power Plant Process Flow Diagram 14
Source: DOE Project Fact Sheet (Modified)

Table 1
Typical Emission Levels and Waste from Coal Based Power Plant Types

2.5% SULFUR EASTERN COAL Source: EPRI With Adjustments By Duke Energy				
PLANT TYPE	SO ₂ EMISSIONS LB/MWH	NO _x EMISSIONS LB/MWH	SOLID WASTE (DRY) LB/MWH	CO ₂ VENT GAS LB/MWH
Pulverized Coal (PC w/ESP Only)	35.7	11.2	136	1871
Pulverized Coal with FGD and LNB (90 percent S Removal, NO, Control	3.6	5.8	232	1908
Atmospheric Fluidized Bed Combustion (AFBC)	3.6	4.9, 0.5 (SNCR)	249	1975
Pressurized Fluidized Bed Combustion (PFBC)	3.3	0.9	230	1826
Integrated Gasification combined cycle (IGCC) (99 Percent S Removal)	0.3	0.9	123	1695
BGL IGCC (99 Percent S Removal, 15 PPM NO.)	0.3	0.4	115	1585
BGL IGFC	0.25	0.18	90	1540

 $^{25^{\}rm o}$ International Technical Conference on Coal Utilization and Fuel Systems March 6-9, 2000 in Clearwater, FL Sent on January 24, 2000

Herrick, Will Campton, KY Page 48 of 108

References:

- 1. U.S. DOE/EIA "Annual Energy Review 1998".
- U.S. DOE/EIA "Annual Energy Outlook 2000".
- Graves, H., Global Energy Inc., Personal Communication, December 1999.
- Farooque, M, G. Steinfeld, G. McCleary, S. Kremenik, "Assessment of Coal Gasification/Carbonate Fuel Cell Power Plants", Topical Report to DOE/METC, June, 1990, DOE/MC/23274-2911. NTIS/DE90015579.
- Sander M.T., et al, Fluor Daniel, G. Steinfeld, Fuel Cell Energy, "Cost and Performance Analysis for a 220 MW Phased Construction Carbonate Fuel Cell Power Plant", 11th Annual Conference on Gasification Power Plants, EPRI, October 1992.
- Sandler H.S., and S.J. Meyers, "Integrated Coal Gasification in Carbonate Fuel Cell Power Plants" 11th Annual Conference on Gasification Power Plants, EPRI, October 1992.
- EPRI, AFPS Developments, Gasification/Fuel Cell Study Projects Very Low Heat Rate, Winter 1990 Issue 6.
- Meyers S., Fluor Daniel, Advanced Molten Carbonate Fuel Cell Systems Using BGL Gasification, Presented at the 9th Annual Conference on Gasification Power Plants, October 16-19, 1990, Palo Alto, CA.
- Rastler, D.M., EPRI, C.G. Keeler, Dow Chemical USA, "Slip Stream Test of a 20 kW Carbonate Fuel Cell Unit at Destec's LGTI GCC Facility", Presented at the EPRI Gasification Conference, Oct 1993.
- Kluttz D.E., Duke Engineering & Services Inc., et al, "Proposed BGL CGCC Project for Clean Coal Technology Round Five Demonstration", Presented at the EPRI Gasification Conference, Oct 1993.
- Steinfeld, G., W. Willson "Advanced Power System Featuring a Closely Coupled Catalytic Gasification Carbonate Fuel Cell Plant" Presented at the 17th Biennial Low-Rank Fuels Symposium, May 10-13, 1993, St. Louis, Missouri.
- Ghezel-Ayagh, H., R. Sanderson, A. J. Leo, "Ultra High Efficiency Hybrid Direct Fuel Cell/Turbine Power Plant", Proceedings of Carbonate Fuel Cell Technology V, PV 99-20, page 297-305, 190th Meeting of the Electrochemical Society, Oct. 7-22, 1999, Hawaii.

25th International Technical Conference on Coal Utilization and Fuel Systems March 6-9, 2000 in Clearwater, FL Sent on January 24, 2000 Herrick, Will Campton, KY Page 49 of 108

- DOE Fossil Energy TechLine, "Richardson Approves Federal Funding for High Tech, Ultra Clean Coal Plant in Kentucky", U.S. DOE Press Release issued November 15, 1999.
- DOE Clean Coal Technology, Compendium, Project Fact Sheet, Advanced Electric Power Generation Integrated Gasification Combined Cycle, Clean Energy Demonstration Project.

 25° International Technical Conference on Coal Utilization and Fuel Systems March 6-9, 2000 in Clearwater, FL. Sent on January 24, 2000

Herrick, Will Campton, KY Page 50 of 108

Appendix D

COMMONWEALTH OF KENTUCKY BEFORE THE PUBLIC SERVICE COMMISSION In the Matter of: In the Matter of: APPLICATION OF EAST KENTUCKY POWER COOPERATIVE, INC. FOR A CERTIFICATE OF PUBLIC CONVENIENCE AND NECESSITY, AND A CERTIFICATE OF ENVIRONMENTAL COMPATIBILITY, FOR THE CONSTRUCTION OF A 250 MW COAL-FIRED
GENERATING UNIT (WITH A CIRCULATING FLUID BED
BOILER) AT THE HUGH L. SPURLOCK POWER STATION BOILER) AT THE HIGHT. SPORGOCK POWER STATION
AND RELATED TRANSMISSION FACILITIES, LOCATED IN
MASON COUNTY, KENTUCKY, TO BE CONSTRUCTED
ONLY IN THE EVENT THAT THE KENTUCKY PIONEER
ENERGY POWER PURCHASE AGREEMENT IS

CASE NO.

CASE NO.
2001-053
OR DE R
East Kentucky Power Cooperative, Inc. ("East Kentucky") filed its application on March 9, 2001 for a Certificate of Public Convenience and Necessity and a Certificate of Environmental Compatibility to construct a 250 MW coal-fired generating unit, referred to as "Gilbert," at the Hugh L. Spurlock power station ("Spurlock") and related transmission facilities in Mason County, Kentucky. The Gilbert unit was to be constructed only in the event that East Kentucky's prior agreement to purchase the current of a 264 MW generating unit monosed by the Kentucky Ploneer Energy LLC. output of a 540 MW generating unit proposed by the Kentucky Pioneer Energy, L.L.C. ("KPE") is terminated. The Attorney General's Office ("AG") and the Kentucky Natural (Nr. L.) Is terminated and Environmental Protection Cabinet, Department of Natural Resources, Division of Energy ("DOE") were granted intervention and a hearing was held on August 18, 2001.

On July 11, 2001, East Kentucky amended its application to eliminate the contingent nature of its request because KPE had not met its financial closing deadline of June 30, 2001. The amended application also revised Gilbert's output from 250 MW of June 30, 2001. In all amendes application also revised calcert's output from 200 was to 268 MW. East Kentucky has not terminated the power purchase agreement because the power will be sold at a very reasonable price and KPE has indicated that it believes it can obtain project financing by March 2002. However, due to the delay in KPE's financing, East Kentucky decided that it cannot reasonably rely on that project to satisfy its future power supply needs. Therefore, East Kentucky has concluded that it should the sold of proceed to build the Gilbert unit. In the event that KPE is able to secure project financing, East Kentucky stated that certain provisions in the existing purchase power agreement would have to be revised and any renegotiated contract will be resubmitted to the Commission for its prior approval

East Kentucky submitted to the Natural Resources and Environmental Protection

Page 49