Review of Generation and Flow of Recycled Uranium at Hanford

Table Of Contents

Page

Executive Summary
- Hanford Recycled Uranium Project 1
- Background 1
- Hanford's Role in Recycled Uranium 1
- Data Examination 2
- Significant Information 2

Section
1.0 Hanford Uranium Mass Balance Project
1.1 Project Overview 1
1.2 Purpose and Scope 1
1.3 Project Implementation Strategy 2
1.4 Assumptions 3
Section 1 References 4

2.0 Hanford Site Historical Overview
2.1 Site Description 1
2.2 Key Uranium Processing Facilities 3
2.2.1 T-Plant 5
2.2.1.1 Plant Description 5
2.2.1.2 T-Plant Material Flowsheet 5
2.2.1.3 Feed Specifications 7
2.2.1.4 Product Specifications 7
2.2.1.5 Operating History 7
2.2.1.6 Current Status 7
2.2.2 B-Plant 8
2.2.2.1 Plant Description 8
2.2.2.2 Material Flowsheet 8
2.2.2.3 Feed Specifications 9
2.2.2.4 Product Specifications 9
2.2.2.5 Operating History 9
2.2.2.6 Current Status 9
2.2.3 U-Plant 10
2.2.3.1 Plant Description 10
2.2.3.2 Material Flowsheet 10
2.2.3.3 Feed Specifications 11
2.2.3.4 Product Specifications 12
2.2.3.5 Operating History 12
2.2.3.6 Current Status 12

Table of Contents

2.2.4 UO_3 Plant 13
2.2.4.1 Plant Description 13
2.2.4.2 Material Flowsheet 14
2.2.4.3 Feed Specifications 17
2.2.4.4 Product Specifications 17
2.2.4.5 Operating History 19
2.2.4.6 Current Status 21
2.2.5 REDOX Plant 21
2.2.5.1 Plant Description 22
2.2.5.2 Material Flowsheet 22
2.2.5.3 Feed Specifications 23
2.2.5.4 Product Specifications 23
2.2.5.5 Operating History 24
2.2.5.6 Current Status 24
2.2.6 PUREX Plant 25
2.2.6.1 Plant Description 25
2.2.6.2 Material Flowsheet 26
2.2.6.3 Feed Specifications 29
2.2.6.4 Product Specifications 29
2.2.6.5 Operating History 29
2.2.6.6 Current Status 31
2.2.7 Fuel Fabrication Complex 32
2.2.7.1 Facility Description 32
2.2.7.2 Material Flowsheet 34
2.2.7.3 Feed Specifications 37
2.2.7.4 Product Specifications 38
2.2.7.5 Operating History 38
2.2.7.6 Current Status 38
2.2.8 Other Uranium Handling Facilities 39
2.2.8.1 308 Building Mixed Oxide Fuel Fabrication 39
2.2.8.2 306 Building 39
2.2.8.3 234-5Z Plutonium Finishing Plant (PFP) 39
2.2.8.4 321 Building 39
2.2.8.5 303-M Uranium Oxide Facility 39
2.3 Activity Summary 40
Section 2 References 42

3.0 Recycled Uranium (see appendices for expanded detail) 1
3.1 Uranium Recycle Description 1
3.1.1 Hanford Key Interfaces for Recycled Uranium 1
3.1.2 Beginning of Hanford In-Scope Recycled Uranium Transactions 8
3.1.2.1 Key Hanford Historical Dates for Recycled Uranium 8
3.1.2.2 Production Channel Material Transactions 8
3.1.2.2.1 Shipments 8
3.1.2.2.2 Receipts 16

Table of Contents

3.1.3 Out of Scope Uranium Transactions....16
3.1.3.1 Hanford Production Channel....16
3.1.3.2 Out-of-Scope Research and Development Programs....17
3.1.3.3 Recycled Uranium Timeframe Summary....18
3.1.4 Data Presentation – Isolation of Specific Timeframes....18
3.1.5 Hanford Historical Timeline References....19
3.1.6 Key Dates/Assumptions for Uranium Transactions....21
3.1.6.1 Beginning Shipment of Recycled Depleted Uranium Trioxide (UO_3)..21
3.1.6.2 Initial Shipments of Recycled Low-Enriched Uranium Trioxide (UO_3)....21
3.2 Recycle Uranium Receipts....22
3.2.1 Uranium Forms Received from Offsite....22
3.2.2 Initial Recycled Uranium Receipts into Hanford....22
3.2.3 Receipts Prior to July 1952 (Out of Scope)....23
3.2.4 Beginning Receipts of Recycled Uranium at Hanford....23
3.2.5 Quantities of Recycled Uranium Received from July 1952 – March 30, 1999....23
3.2.6 Hanford Receipts of Recycled Uranium from Paducah....24
3.2.7 Hanford Receipts of Recycled Uranium from Fernald and RMI (Ashtabula)....24
3.2.8 Hanford receipts of Recycled Uranium from Oak Ridge....24
3.3 Recycle Uranium Shipments....24
3.3.1 Recycled Uranium Streams Shipped Offsite....24
3.3.2 Uranium Shipments from 300 Area Fuel Fabrication Facilities....28
3.3.3 Hanford Shipments of Recovered Uranium and Trioxide Product....32
3.3.3.1 UO_3 Finished Product....32
3.3.3.2 Introduction of Fission Products....32
3.3.4 Out-of-Scope Research and Development Spent Fuel....33
3.3.5 Post Fiscal Year 1970 Shipments....35
3.3.6 Shipment Packaging and Scheduling....35
3.3.7 Transaction Material Control and Accountability (MC&A)....35
3.3.8 Sample Exchange Program and Sample Shipments....35
3.4 Recycle Uranium Scrap, Waste, and Conversion....36
3.4.1 Introduction....36
3.4.2 Reactor Fuel Element Fabrication....36
3.4.2.1 Scrap Returned to Fernald....38
3.4.2.2 Liquid Effluent - Chemical Waste Containing Uranium....38
3.4.2.3 Airborne Effluents....40
3.4.2.4 Solid Waste....40
3.4.2.5 300 Area Process Trenches....40
3.4.3 Hanford Separation Plants....40
3.4.4 Recovery of Uranium in the U-Plant....41
3.4.5 Uranium Trioxide (UO_3) Plant....41
3.4.6 Summary of Uranium Discharged to Wastes at Hanford....42
3.4.7 Uranium Losses Through Transmutation and Fission....43
3.5 Overall Recycled Uranium Site Material Balance....43

Table of Contents

Section 3 References....48

4.0 Contaminants in Recycled Uranium 1
4.1 UO_3 Process Specifications 1
4.1.1 Feed Specifications....1
4.1.2 Product Specifications....2
4.1.3 Proposed Specifications....2
4.1.4 Non-Radiological Contaminants....3
4.2 Recycle UO_3 Processing....4
4.2.1 Processing Issues....5
4.2.2 Typical Hanford Responses....5
4.3 Analytical Laboratories....7
4.3.1 UO_3 Product Sampling and Subsampling....7
4.3.2 Analytical Procedures....8
4.3.3 Analytical Methods and Errors....10
4.3.4 Quality Assurance....11
4.3.4.1 Quality Assurance Program....11
4.3.4.2 In-House Standards Program....12
4.4 UO_3 Analyses....13
4.4.1 Impurity Concentrations in UNH....13
4.4.2 Analyses Performed and Results....13
4.4.3 Storage/Shipment of UO_3....14
4.4.4 Storage of UO_3 at Hanford....15
4.4.5 UO_3 Processed In/After 1984 Restart of PUREX/UO_3 Plants....18
4.5 Neptunium-237....18
4.5.1 Neptunium Concentration in Recycled Uranium....18
4.5.2 Neptunium-237 (^{237}Np) Formation....18
4.5.3 Predicted vs. Actual ^{237}Np Production....20
4.5.4 Enhancing Production of Neptunium....20
4.6 Technetium-99 Analytical Results....22
4.6.1 Technetium-99 Concentration in Recycled Uranium....22
4.6.2 Hanford Technetium Measurements....22
4.6.3 Paducah Measurements of Technetium-99 in Recycled Uranium from Hanford....23
4.6.4 Fernald Measurements of Technetium-99 in Recycled Uranium from Hanford....23
4.7 Uranium Isotopic Composition....23
4.7.1 Natural Uranium....23
4.7.2 Normal Uranium....24
4.7.3 Low Enriched Uranium (LEU)....24
4.7.4 Typical Recovered LEU Uranium Oxide....24
4.8 Contaminants in Uranium Metal....27
4.8.1 Non-radiological Composition....27
4.8.2 Metallographic Testing....28
4.8.3 Radiological Contaminants....28
4.8.4 Direct Blending....29

Table of Contents

Section 4 References 31

5.0 Current Inventory of Recycled Uranium 1
5.1 Current Hanford Management Contractor (PHMC) Inventory of Recycled Uranium 1
5.2 Pacific Northwest National Laboratories(PNNL) Current Inventory of Recycled Uranium 2

6.0 Discussion and Conclusions 1
6.1 Recycled Uranium Shipped and Received 1
6.1.1 Operating History 1
6.1.2 Recycled Uranium Specifications 1
6.1.3 Recycled Uranium Shipments and Receipts 1
6.1.4 Current Inventory 2
6.1.5 Shipper/Receiver Differences 2
6.1.6 Inventory Difference 2
6.2 Typical Impurities and Isotopic Composition 3
6.2.1 Plutonium 3
6.2.2 Neptunium and Technetium 3
6.3 Activity Assessment and Occupational Potential Exposure 4
6.4 Data Validation 10
6.4.1 Recycled Uranium Shipped from Hanford 10
6.4.2 Impurities Shipped with UO_3 from Hanford 10
6.4.3 Discussion of Pu Differences Between K-25 and Hanford 11
Section 6 References 16

Table of Contents

Tables

Section 3

Table 3-1	Total Recycled Uranium Received from Offsite Sources	24
Table 3-2	Hanford Receipts from Paducah	25
Table 3-3	Hanford Receipts from Fernald	26
Table 3-4	Hanford Receipts from Oak Ridge (K-25 & Y-12)	27
Table 3-5	Summary of Recycled Uranium Shipments from Hanford	28
Table 3-6	Hanford Uranium Shipments to Paducah	29
Table 3-7	Hanford Summary Shipments to Fernald in MTU	30
Table 3-8	Hanford Summary Shipment to Oak Ridge (K-25 & Y-12)	31
Table 3-9	Uranium Waste at Hanford	42
Table 3-10	Hanford Mass Balance-Total In-Scope & Out-of-Scope	45

Section 4

Table 4-1	UO_3 Process Specifications	3
Table 4-2	Summary of UO_3 Shipments in 1952 and LEU 1967-1972	14
Table 4-3	Summary of Drummed UO_3 Product	16
Table 4-4	Analyses of UO_3 Produced In/After 1984 at Hanford	19
Table 4-5	Special Process Batch	20
Table 4-6	Calculated Production of Neptunium in Hanford Reactors	20
Table 4-7	Neptunium Analyses on UNH	22
Table 4-8	Typical Uranium Isotopic Ratio of LEU Produced In/After 1970	25
Table 4-9	Deeply Depleted UO_3 Isotopic Data	25
Table 4-10	^{235}U Isotopic Data of Pre-1972 Product or Depleted UO_3	26
Table 4-11	Chemical Specifications for Uranium Metal Billets	27
Table 4-12	Transuranic Content in Ingot Composites	30

Section 6

Table 6-1	Assessment of Activities at Hanford Where Workers Were Most Likely to Contact Recycled Uranium	5

Table of Contents
Figures

Section 1

Figure 1-1	Hanford Recycled Uranium Project Functional Breakdown	3

Section 2

Figure 2-1	The Hanford Site, Richland, Washington	2
Figure 2-2	Hanford Major Process Flows and Facility Interfaces	4
Figure 2-3	T-Plant Process Flow Diagram	6
Figure 2-4	Simplified U-Plant Tributyl Phosphate (TBP) Process Flow Diagram	11
Figure 2-5	UO_3 Plant Process Diagram Involving Batch Pot Calciners	14
Figure 2-6	UO_3 Plant Process Diagram Involving Continuous Calciners	15
Figure 2-7	UO_3 Product Loadout System	16
Figure 2-8	Copy of Early UO_3 Product Specification	19
Figure 2-9	REDOX Process Flow Diagram (Simplified)	23
Figure 2-10	PUREX Process Flow Diagram (Excluding the Plutonium Production and Rework Facilities)	27
Figure 2-11	Example of PUREX Production Specification	30
Figure 2-12	Early Photograph of Fuel Fabrication Facilities in the 300 Area	33
Figure 2-13	Fuel Fabrication Process for Single-Pass Reactors	35
Figure 2-14	N Reactor Fuel Fabrication Process	36
Figure 2-15	303-M Uranium Oxide Facility	40
Figure 2-16	Operating Intervals During Which Major Hanford Facilities Processed Recycled Uranium	41

Section 3

Figure 3-1	Major "Tier 1" Sites for Hanford Recycled Uranium Transactions	2
Figure 3-2	Major DOE Field Facilities	3
Figure 3-3A	Material Flow-Manhattan Engineer District: 1942-1946	4
Figure 3-3B	Material Flow-Atomic Energy Commission: 1946-mid 1950s	5
Figure 3-3C	Material Flow-Atomic Energy Commission: mid 1950s-mid 1960s	6
Figure 3-3D	Material Flow-Atomic Energy Commission/Energy Research and Development Agency/Department of Energy: mid 1960s-late 1980s	7
Figure 3-4A	First Hanford Shipment of UO_3 Containing Transuranics & Analytical Data	9
Figure 3-4B	Second Hanford Shipment Containing Transuranics and Analytical data	11
Figure 3-5	Example of Historical Transfer Forms-Cover Page	13
Figure 3-5 (Cont)	Example of Historical Transfer Form for Shipment from Hanford to Paducah (circa 1971)	14
Figure 3-6	Product Acceptance Form Hanford Depleted UO_3 to Paducah (circa 1971)	15
Figure 3-7	1949 Schematic Diagram Showing Uranium Flow in 300 Area	17

Table of Contents

Figure 3-8	Typical Metal Billet Receipt Inbound from RMI/Fernald in the 1980s	22
Figure 3-9	UO_3 T-Hoppers at Hanford Rail Spur, 200 West Area	34
Figure 3-10	Uranium Flow and Inventory in Fuels Manufacturing Process (CY 1978)	38
Figure 3-11	Waste Acid and Uranium-Bearing Acid Recovery System	39
Figure 3-12	Hanford Uranium Mass Flow	47
Section 4		
Figure 4-1	Example Page of Specifications for UO_3 Plant	4
Section 5		
Figure 5-1	Hanford Total PHMC Uranium Inventory	1
Section 6		
Figure 6-1	Estimate of Personnel Having Work Potentially Involving Exposure to Recycled Uranium at Specific Facilities	8
Figure 6-2	Plutonium Contained in Recycled Uranium Shipped from Hanford	12
Figure 6-3	Neptunium Contained in Recycled Uranium Shipped from Hanford	13
Figure 6-4	Neptunium Contained in Recycled Uranium Shipped from Hanford	14

Table of Contents

Appendices

Appendix A	**Acronyms and Glossary of Terms**	
	Acronyms	2
	Glossary of Terms	6
Appendix B	**Section 3 - Supplemental Information**	
Table 3.2.1	Out-of-Scope Hanford Receipts (as reference)	3
Table 3.2.2	1950-FY 65 Hanford (GE Company) Uranium Receipts from Offsite	8
Table 3.2.3	Hanford FY 1966-70 Uranium Receipts	21
Table 3.2.4	Hanford Chemical Processing Contractor (HVA) Uranium Receipts FY 1971-March 31, 1999	28
Table 3.2.5	Hanford Chemical Processing Contractor (HRA) Uranium Receipts FY 1971-March 31, 1999	30
Table 3.2.6	Hanford Chemical Processing Contractor (HUD & HTA) Uranium Receipts FY 1971-March 31, 1999	32
Table 3.2. 7	Hanford Reactor/Fuel Fab Contractor (HXA) Uranium Receipts FY 1971-March 31, 1999	34
Table 3.2.8	Pacific Northwest National Laboratory (PNNL) Uranium Receipts FY 1965-March 31, 1999	36
Table 3.3.1	December 1947 Through June 51 Hanford (GE Company) Uranium Shipments Offsite	38
Table 3.3.2	FY 1952-65 Hanford (GE Company) Uranium Shipments to Offsite Locations	47
Table 3.3.3	FY 1966-70 Hanford Uranium Offsite Shipments	60
Table 3.3.4	Hanford Chemical Processing Contractor (HVA) Uranium Shipments FY 1971-March 31, 1999	64
Table 3.3.5	Hanford Chemical Processing Contractor (HRA) Uranium Shipments FY 1971-March 31, 1999	66
Table 3.3.6	Hanford Chem. Processing Contrs (HUD & HTA) Uranium Shipments FY 1971-March 31, 1999	68
Table 3.3.7	Hanford Reactor Contractor (HXA) Uranium Shipments FY 1971-March 31, 1999	70
Table 3.3.8	Pacific Northwest National Laboratory (PNNL) Offsite Uranium Shipments	72
Appendix C	**Section 4 - Supplemental Information**	
Table 4-1	Detailed Analyses of 1952 Produced UO_3	2
Table 4-2	Detailed Analysis of LEU UO_3	3
Table 4-3	Detailed Analysis of Drummed UO_3 Product	6

Table of Contents

Appendix D	**Section 5 - Supplemental Information**	
Table 5.1.1	Current Inventory of Hanford In-Scope Uranium	2
Table 5.1.2	Pacific Northwest National Laboratory (PNNL) Recycled Uranium Inventory as of March 31, 1999	5
Appendix E	**Description of Research Strategies Used in Study**	
E.0	Uranium Mass Balance Project Document Retrieval and Review Process	2
Figure E-1	Complexity and Range of Information to be Researched at Hanford	2
Figure E-2	Uranium Mass Balance Project Document Identification/Review Process	3
E.1	Databases Used	4
E.2	Database Keyword Searches	5
Table E-1	Keywords Used in Searching Databases	7
E.3	Technical Review of Keyword Search Results	7
E.4	Obtaining Documents and Boxes of Records	8
E.5	Additional Document Searches	9
E.6	Technical Review of Documents	9
E.7	Project Records	9
E.8	References	10
Appendix F	**Supplemental Information on Hanford Fuel Fabrication**	
F.1	Single Pass Reactor Fuel Fabrication	3
F.1.1	Fuel Canning	3
F.1.2	Single Pass Fuel Fabrication Changes	4
F.2	N-Reactor Fuel Fabrication Processing	5
F.2.1	N-Reactor Fuel Fabrication	5
F.2.2	Co-Extrusion Process	6
F.3	Material Sources	7
F.4	References	8
Appendix G	**Supplemental Information on the UO_3 Plant**	
G.1	Operating History Uranium Trioxide (UO_3) Plant	3
G.2	Process Operations	6
G.3	Waste Generation	7
G.4	Radiation Exposure	8
G.5	Contaminate Partitioning	8
G.6	UO_3 Related Incidents	9
G.7	References	10

Table of Contents

Appendix H Timeframe of Events at Hanford

Appendix I Estimates of Annual Recycled Uranium Constituents Shipped Offsite

Table I-1 Historical Hanford Recycled Uranium Receipts (MTU) 4
Table I-2 Historical Hanford Recycled Uranium Shipments (MTU) 5
Table I-3 Estimated Minimum Pu in Historical Hanford Recycled Uranium Shipments (Gm) 6
Table I-4 Estimated Mean Pu in Historical Hanford Recycled Uranium Shipments (Gm) 7
Table I-5 Estimated Maximum Pu in Historical Hanford Recycled Uranium Shipments (Gm) 8
Table I-6 Estimated Minimum Np in Historical Hanford Recycled Uranium Shipments (Kg) 9
Table I-7 Estimated Mean Np in Historical Hanford Recycled Uranium Shipments (Kg) 10
Table I-8 Estimated Maximum Np in Historical Hanford Recycled Uranium Shipments (Kg) 11
Table I-9 Estimated Minimum Tc in Historical Hanford Recycled Uranium Shipments (Kg) 12
Table I-10 Estimated Mean Tc in Historical Hanford Recycled Uranium Shipments (Kg) 13
Table I-11 Estimated Maximum Tc in Historical Hanford Recycled Uranium Shipments (Kg) 14
Table I-12 Estimated Constituents Based On Low Value Of Constituent Boundary Range 15
Table I-13 Estimated Constituents Based On Mean Value Of Constituent Boundary Range 16
Table I-14 Estimated Constituents Based On High Value Of Constituent Boundary Range 17